

Employer's Requirements (Extract)

Kestrel Flyover Interchange Project — Package KFI-2

Document Reference:	KFI2-ER-2019
Date:	20-May-2019
Contract No.:	KMDA/KFI2/CW/2019-04
From:	Kaldera Metropolitan Development Authority (Employer)
To:	Ashgrove Infrastructure Consultants (Engineer); Rennick Builders Ltd. (Contractor)

This document sets out the Employer's technical requirements for the construction and commissioning of the Works. It is a technical requirements document and does not form the Conditions of Contract. This is an extract; matters not addressed below are not to be taken as excluded from the Contractor's obligations under the Contract.

1. PROJECT OVERVIEW

The Works comprise the design (to the extent stated in the Specification), construction and commissioning of an elevated flyover interchange connecting Highway N-7 and Ring Road R-2 at Rostam Central Junction, together with all ancillary civil, structural, drainage and signage works necessary for the interchange to be brought into safe public use. The Works are located within Verrin District, Rostam City, Republic of Kaldera.

2. SCOPE OF WORKS

The Scope of Works includes, without limitation: site clearance and preparatory works; temporary traffic management and diversion for the duration of construction; foundation and substructure works, including piling, pile caps and piers; superstructure works, including precast girders, deck slab, parapets, expansion joints and bearings; ramp and approach works connecting to Highway N-7 and Ring Road R-2; permanent signage, lighting conduit and road marking within the limits of the Works; and testing and commissioning of the completed structure.

3. STRUCTURE CONFIGURATION

The flyover shall comprise 6 spans with an overall length of approximately 480 metres, supported on 2 abutments and 5 piers, carrying a dual two-lane carriageway with hard shoulders over Rostam Central Junction. The Works shall be designed and constructed for a design life of 100 years, in accordance with the Kaldera National Bridge Design Code and the Specification.

4. PROGRAMME AND RESOURCING

The Contractor shall maintain, and resource the Works in accordance with, a programme complying with Section 5 of this document, updated monthly, showing planned versus actual progress by principal element (piling, substructure, superstructure, ramps, finishing works). The Contractor shall deploy labour, plant and supervision consistent with the resource levels stated in its accepted programme, and shall notify the Engineer promptly of any material shortfall in resourcing and the reason for it.

5. PROGRAMME REQUIREMENTS

KESTREL FLYOVER INTERCHANGE PROJECT

Package KFI-2

EMPLOYER'S REQUIREMENTS (EXTRACT)

The Contractor's programme shall show a planned percentage of overall contract value complete at each monthly reporting date, against which actual progress is to be measured and reported in the Contractor's monthly progress report. A shortfall of more than 15 percentage points between planned and actual overall progress at any reporting date, sustained for two or more consecutive reporting periods, shall be treated by the Engineer as a material indicator of a failure to proceed with due diligence for the purposes of Sub-Clause 15.1.

6. QUALITY AND RECORDS

The Contractor shall maintain a Site diary, monthly progress reports, and measurement records sufficient to support Statements submitted under the Contract, and shall retain all such records for inspection by the Engineer. Utilities shown on the Drawings, including a water main crossing the Site near Ramp C, are based on records supplied by the relevant utility owner and may not be complete; the Contractor shall verify utility locations before excavation and report promptly any utility encountered that is not shown on the Drawings.

[END OF EMPLOYER'S REQUIREMENTS EXTRACT]
