

Method Statement — Crack Injection Repair, Pier P2 Pier Cap

Nandira River Bridge Project — Package NRB-4

Document Reference:	MST-NRB4-001
Date:	10-Jun-2024
Contract No.:	NHIA/NRB4/CW/2020-01
From:	Contractor, Quality Manager, Sagara Constructions Pvt. Ltd.
To:	Engineer, Meridian Engineering Consultants

Subject: Method Statement Submitted Under SI-NRB4-031 — Pier P2 Pier Cap

SCOPE:

Low-viscosity epoxy resin injection of all cracks 0.2mm and greater identified in Crack Mapping Report CMR-NRB4-001 (approximately 45 linear metres of crack, concentrated in grid zones B2-E6), followed by application of a penetrating, breathable surface sealer across the full top surface of the pier cap, in accordance with Site Instruction SI-NRB4-031.

SEQUENCE OF WORK:

- 1. Surface preparation: cleaning and degreasing of all crack lines and surrounding surface by low-pressure water wash and air drying.
- 2. Injection port installation at 150mm centres along each crack line 0.2mm or greater, surface-sealed with epoxy paste pending injection.
- 3. Low-viscosity epoxy resin injection under controlled pressure, working from the lowest port upward along each crack line, until resin return is observed at the adjacent port.
- 4. Minimum 48-hour cure before port removal and surface grinding flush.
- 5. Application of penetrating, breathable surface sealer across the full top surface, in two coats, following manufacturer's recoat interval.
- 6. Re-survey of the treated area against the SIR-NRB4-001 reference grid, and preparation of the Rectification Completion Report.

MATERIALS:

Structural epoxy injection resin and surface sealer, both proprietary products with manufacturer's technical data sheets and third-party test certification confirming suitability for structural crack injection and exposed concrete surfaces respectively, to be submitted with product samples for the Engineer's review before procurement.

QUALITY CONTROL:

Injection pressure and resin consumption per linear metre to be logged for each crack line. A minimum of 3 no. injected sections will be selected at random by the Engineer for verification coring after cure, to confirm full resin penetration through the crack depth.

Submitted by: Quality Manager, Sagara Constructions Pvt. Ltd.