

Contractor's Variation Quotation — VO-NRB4-004

Nandira River Bridge Project — Package NRB-4

Document Reference:	CTR-NRB4-0067
Date:	22-Oct-2021
Contract No.:	NHIA/NRB4/CW/2020-01
From:	Contractor, Sagara Constructions Pvt. Ltd.
To:	Engineer, Meridian Engineering Consultants

Subject: Variation Quotation — VO-NRB4-004 — Pier P3 Pile Cap Redesign

In accordance with Sub-Clause 13.3 and Variation Order VO-NRB4-004, we submit our priced quotation for the varied works shown on drawing DRG-NRB4-P3-PC-Rev02.

COST BREAKDOWN:

Item	Description	Qty	Rate (VTD)	Amount (VTD)
1	Additional excavation and disposal of backfill	48 m3	1,850/m3	88,800
2	Mass concrete replacement fill, Grade M20	22 m3	6,400/m3	140,800
3	Additional reinforced concrete, Grade M40	28 m3	8,200/m3	229,600
4	Additional reinforcement steel	3.1 t	42,000/t	130,200
5	Additional formwork to enlarged pile cap edge	38 m2	1,450/m2	55,100
6	Disruption and extended standing time, plant and crew, Pier P3, 14 days	LS	—	42,900
			TOTAL:	VTD 687,400

Items 1–5 are priced by reference to Contract rates for comparable items in the Bill of Quantities, adjusted where no directly comparable rate exists, in accordance with Sub-Clause 13.3. Item 6 reflects standing time for plant and crew mobilised to the affected zone during the period between notice CTR-NRB4-0061 and issue of drawing DRG-NRB4-P3-PC-Rev02, during which work on the affected portion of the pile cap could not proceed.

Supporting quantity calculations and delivery records are available for the Engineer's inspection.

SAGARA

Constructions Pvt. Ltd.
Sagara Constructions Pvt. Ltd.
Sagara House, 8 Industrial Estate Road, Vantara City

VARIATION QUOTATION

Regards,
Project Manager / Quantity Surveyor
Sagara Constructions Pvt. Ltd.